



**Total permitted animal capacity from all permits for this site:**  
200,000 chicken broilers

---

In consideration of Decision Summary RA24012, Approval RA24012 is issued to:

Name: Both's Custom Works Ltd. (the "permit holder")  
Address: RR 2 Ponoka, AB T4J 1R2  
Contact person: Peter Both

**Permitted construction** (based on the submitted site plan):

- Chicken broiler barn (3<sup>rd</sup> from north) – 128 m x 20.11 m
- Chicken broiler barn (4<sup>th</sup> from north) – 128 m x 20.11 m

**Ancillary structures** (based on submitted site plan):

- Attached service room to broiler barns – 15.24 m x 38.1 m

The permit holder shall comply with the requirements of the *Agricultural Operation Practices Act* (AOPA) and the regulations passed pursuant to that Act.

The permit holder shall adhere to the descriptions contained in the filed applications RA24012 and RA19032, together with the site plan, building plans, and other attached documents included, unless otherwise noted in the following conditions.

The permit holder shall contact the NRCB at least 10 working days in advance of the desired inspection date to schedule the inspection in conditions 2 and 5.

The permit holder is responsible for all costs associated with sampling, testing, recording, and reporting requirements (this includes post construction reports).

### **Construction conditions**

New chicken broiler barn (3<sup>rd</sup> from north)

1. The concrete used to construct the liner of the new chicken broiler barn must meet the specifications for category D (solid manure – dry), in Technical Guideline Agdex 096-93 "Non-Engineered Concrete Liners for Manure Collection and Storage Areas." The permit holder shall provide written confirmation, from a qualified third party, confirming that the concrete used for the manure collection and storage areas meets the required specification.
2. The permit holder shall not allow birds or manure in the new chicken broiler barn, until the facility has been inspected by NRCB personnel and confirmed by them, in writing, to have been constructed in accordance with the terms and conditions of this permit.
3. The permit holder shall complete construction of the manure collection and storage portions of the new chicken broiler barn prior to December 10, 2025. Upon request, this deadline may be extended by the NRCB in writing.



New chicken broiler barn (4<sup>th</sup> from the north)

4. The concrete used to construct the liner of the new chicken broiler barn must meet the specifications for category D (solid manure – dry), in Technical Guideline Agdex 096-93 “Non-Engineered Concrete Liners for Manure Collection and Storage Areas.” The permit holder shall provide written confirmation, from a qualified third party, confirming that the concrete used for the manure collection and storage areas meets the required specification.
5. The permit holder shall not allow birds or manure in the new chicken broiler barn, until the facility has been inspected by NRCB personnel and confirmed by them, in writing, to have been constructed in accordance with the terms and conditions of this permit.
6. The permit holder shall complete construction of the manure collection and storage portions of the new chicken broiler barn prior to December 10, 2025. Upon request, this deadline may be extended by the NRCB in writing.

This approval becomes effective immediately. The approval conditions will remain in effect unless amended in writing by the NRCB.

Approval RA19032 is hereby superseded, and its content consolidated into this Approval RA24012, unless Approval RA24012 is held invalid following a review and decision by the NRCB’s board members or by a court, in which case Approval RA19032 will remain in effect.

June 10, 2024

(Original signed)

Lynn Stone  
Approval Officer



**Approval RA24012 – Appendix**

<b>Facility</b>	<b>Dimensions (m)</b>	<b>From</b>
Barn 1 (north)	128 m x 20.1 m	Approval RA19032
Barn 2 (south)	128 m x 20.1 m	Approval RA19032