



**Total permitted animal capacity from all permits for this site:**  
35,000 chicken layers

---

In consideration of Decision Summary RA24049, Approval RA24049 is issued to:

Name: Hutterian Brethren Church of Rosewood and Rosewood Colony Holdings  
Inc. (the “co-permit holders”)  
Address: Box 116 Czar, AB T0B 0Z0  
Contact person: Mike Wurz

**Permitted construction** (based on the submitted site plan):

- Layer barn – 59.7 m x 18.7 m with attached manure storage 18.7 m x 9.1 m

**Ancillary facilities**

- Egg packaging/sorting facility and office area

The co-permit holders shall comply with the requirements of the *Agricultural Operation Practices Act* (AOPA) and the regulations passed pursuant to that Act.

The co-permit holders shall adhere to the descriptions, building plans, and other attached documents included with filed Application RA24049 and Registration RA16074.

The co-permit holders shall contact the NRCB at least 10 working days in advance of the desired inspection date to schedule the inspection in condition 3.

The co-permit holders are responsible for all costs associated with recording and reporting requirements (this includes post construction reports).

**Construction conditions**

Layer Barn

1. The concrete used to construct the liner of the manure collection and storage portions of the new layer barn shall meet the specification for category D (solid manure – dry) in Technical Guideline Agdex 096-93 “Non-Engineered Concrete Liners for Manure Collection and Storage Areas”.
2. The co-permit holders shall provide documentation to confirm the specifications of the concrete used to construct the manure storage and collection portions of the new layer barn.
3. The co-permit holders shall not allow livestock or manure in the new layer barn until the facility has been inspected by NRCB personnel and confirmed by them, in writing, to have been constructed in accordance with the terms and conditions of this permit.



4. The co-permit holders shall complete construction of the manure collection and storage portions of the new layer barn prior to November 30, 2027. Upon request, this deadline may be extended by the NRCB in writing.

This approval becomes effective immediately. The approval conditions will remain in effect unless amended in writing by the NRCB.

Previously issued Registration RA16074 is hereby superseded, and its content consolidated into this Approval RA24049, unless Approval RA24049 is held invalid following a review and decision by the NRCB's board members or by a court, in which case Registration RA16074 will remain in effect.

February 26, 2025

(Original signed)

Sarah Neff  
Approval Officer



---

## Approval RA24049 – Appendix

### Existing permitted facilities

Facility	Dimensions (m)	Permit
Layer barn with attached manure storage	86.7 m x 15.8 m	RA16074

### Construction conditions (previously met conditions from Registration RA16074)

- 1. Concrete**  
The concrete used to construct the manure storage and collection system in the layer barn and its attached manure storage area must have a minimum 28-day compressive strength of 25 MPa. The permit holder shall provide written proof to the NRCB to confirm the specifications of the concrete used in the construction. This document must be provided to the NRCB prior to the inspection referenced in condition 3, below, or by a later date stated by the NRCB.
- 2. Construction completion deadline**  
The permit holder shall complete construction of the manure collection and storage portions of the layer barn and its attached manure storage area prior to July 1, 2021. Upon request, this deadline may be extended by the NRCB in writing.
- 3. Post construction inspection**  
The permit holder shall not place livestock or manure in the layer barn or its attached manure storage area until the NRCB has inspected it and stated in writing that the facilities has been constructed in accordance with this registration.